

ORDINANCE NO. 2019-055

AUTHORIZING THE VILLAGE MANAGER TO ENTER INTO A CONTRACT WITH BOONE WATER SYSTEMS, INC IN AN AMOUNT NOT TO EXCEED \$59,140 FOR THE DRILLING OF WELL 9 AND DECLARING AN EMERGENCY

WHEREAS, the Village of Waynesville has requested proposals for well drilling services; and
WHEREAS, Boone Water Systems, Inc. submitted the lowest and best proposal for said work with a proposal of \$59,140.

7 NOW, THEREFORE, BE IT ORDAINED by the Village Council of the Village of Waynesville, members elected thereto concurring:

Section 1. The Village of Waynesville accepts the specifications and agrees that Boone Water Systems, Inc. has submitted the best proposal.

Section 2. That the Village Manager is hereby authorized to enter into a contract with Boone Water Systems, Inc. for the drilling of well 9.

Section 3. That the Finance Director is hereby authorized to pay a sum not to exceed \$59,140 for said work in accordance with the proposal attached hereto and incorporated herein by reference.

Section 4. That this Ordinance is hereby declared to be an emergency measure necessary for the preservation of the public peace, health, safety, and general welfare and shall be effective immediately upon its adoption. The reason for said declaration of emergency is the critical need to increase water production to keep up with the demand and take advantage of appropriate weather conditions.

Adopted this 7th day of October, 2019.

Attest:

✓

✓

Boone Water Systems, Inc.

Well Drilling Contractors "Since 1868"
 1001 Van Eaton Rd.
 Xenia, Oh. 45385

Ph. 937-376-4572
 email :
 boonedrill@yahoo.com

Estimate

Date	Estimate #
9/17/2019	89-959

Name / Address
Groundwater Science Allan Comeskey 295 S. Lawn Ave. Bluffton, Oh. 45817

Ship To
Village of Waynesille, Oh.

Terms	Project
Due Upon Receipt	

Item	Description	Qty	Cost	Total
Mobilization	mob/set-up/set 10' 30" surface casing	1	2,500.00	2,500.00
Drill	drill case 20" diameter cable tool hole to 62 ft. depth	1	18,000.00	18,000.00
Screen	furnish, install 17 ft. Johnson type 304 stainless steel 12" pipe size v-wire well screen	1	8,900.00	8,900.00
Pipe	furnish, install 50 ft. 12" .375 wall carbon steel pipe/riser	50	80.00	4,000.00
filter pack	35 cu/ft no. 4 Global filter pack installed	1	3,000.00	3,000.00
Development	apply 24 hrs. combination air surge	24	180.00	4,320.00
test pump	furnish, install temporary 500 gpm submersible test pump, orifice, throttle valve, est. 700 ft. temporary discharge piping, remove upon completion of test	1	8,500.00	8,500.00
generator	furnish 65 KW generator and fuel to conduct step test and 24 hr. constant rate test	1	1,500.00	1,500.00
Crew	2 man crew conduct step drawdown test	1	900.00	900.00
Test	2 man crew split shift 24 hr. constant rate test	24	105.00	2,520.00
Lab Fee	OEPA new well analysis lab fee	1	1,500.00	1,500.00
Grout	grout 0-25 ft. annulus with hole plug and benseal slurry	1	3,500.00	3,500.00
Standard wage rates apply, No bonding requirements or additional insurance requirements City will assist in access in foul weather if required				

Acceptance Signature:	Total	\$59,140.00
-----------------------	--------------	-------------

Boone Water Systems, Inc. does not guarantee water quantity or quality (iron, hardness, sulphur, bacteria, etc.) The cost of one initial chlorination is included in this estimate. Any additional chlorination/sampling deemed necessary by Health Dept. will be charge additional.
 937-376-4572